

OKLAHOMA CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
P.O. BOX 52000  
OKLAHOMA CITY, OK 73152-2000  
(Rule 165:10-3-1)

API NUMBER: 011 23984

Approval Date: 04/16/2018

Expiration Date: 10/16/2018

Horizontal Hole Oil & Gas

PERMIT TO DRILL

WELL LOCATION: Sec: 04 Twp: 15N Rge: 10W County: BLAINE  
SPOT LOCATION:     FEET FROM QUARTER: FROM NORTH FROM WEST  
SECTION LINES: 250 1320

Lease Name: DOPPELGANGER 4\_9-15N-10W Well No: 3HX Well will be 250 feet from nearest unit or lease boundary.  
Operator Name: DEVON ENERGY PRODUCTION CO LP Telephone: 4052353611; 4052353 OTC/OCC Number: 20751 0

DEVON ENERGY PRODUCTION CO LP  
333 W SHERIDAN AVE  
OKLAHOMA CITY, OK 73102-5015

LOOSEN FAMILY LIMITED PARTNERSHIP  
P. O. BOX 1337  
OKLAHOMA CITY OK 73101-

Formation(s) (Permit Valid for Listed Formations Only):

	Name	Depth	Name	Depth
1	MISSISSIPPIAN (EX CHESTER)	10178	6	
2	WOODFORD	10803	7	
3			8	
4			9	
5			10	

Spacing Orders: 658264  
658265

Location Exception Orders:

Increased Density Orders:

Pending CD Numbers: 201801336  
201801335  
201801339  
201801340

Special Orders:

Total Depth: 20355 Ground Elevation: 1316 Surface Casing: 1999 Depth to base of Treatable Water-Bearing FM: 40

Under Federal Jurisdiction: No

Fresh Water Supply Well Drilled: No

Surface Water used to Drill: Yes

PIT 1 INFORMATION

Approved Method for disposal of Drilling Fluids:

Type of Pit System: CLOSED Closed System Means Steel Pits

Type of Mud System: WATER BASED

Chlorides Max: 8000 Average: 5000

Is depth to top of ground water greater than 10ft below base of pit? Y

Within 1 mile of municipal water well? N

Wellhead Protection Area? N

Pit is not located in a Hydrologically Sensitive Area.

Category of Pit: C

Liner not required for Category: C

Pit Location is NON HSA

Pit Location Formation: FLOWERPOT

D. One time land application -- (REQUIRES PERMIT) PERMIT NO: 18-34239  
H. SEE MEMO

This permit does not address the right of entry or settlement of surface damages.  
The duration of this permit is SIX MONTHS, except as otherwise provided by Rule 165: 10-3-1.  
Rule 165: 10-3-4 (c) (7) (e) - The Operator shall give 24 Hours notice by telephone to the appropriate District Office of the Conservation Division as to when Surface Casing will be run.

PIT 2 INFORMATION

Type of Pit System: CLOSED Closed System Means Steel Pits

Type of Mud System: OIL BASED

Chlorides Max: 300000 Average: 200000

Is depth to top of ground water greater than 10ft below base of pit? Y

Within 1 mile of municipal water well? N

Wellhead Protection Area? N

Pit is not located in a Hydrologically Sensitive Area.

Category of Pit: C

Liner not required for Category: C

Pit Location is NON HSA

Pit Location Formation: FLOWERPOT

HORIZONTAL HOLE 1

Sec 09 Twp 15N Rge 10W County BLAINE

Spot Location of End Point: SW SW SE SW

Feet From: SOUTH 1/4 Section Line: 50

Feet From: WEST 1/4 Section Line: 1510

Depth of Deviation: 9355

Radius of Turn: 477

Direction: 179

Total Length: 10251

Measured Total Depth: 20355

True Vertical Depth: 10803

End Point Location from Lease,  
Unit, or Property Line: 50

Notes:

Category

Description

DEEP SURFACE CASING

4/4/2018 - G71 - APPROVED; NOTIFY OCC FIELD INSPECTOR IMMEDIATELY OF ANY LOSS OF CIRCULATION OR FAILURE TO CIRCULATE CEMENT TO SURFACE ON ANY CONDUCTOR OR SURFACE CASING

HYDRAULIC FRACTURING

4/4/2018 - G71 - OCC 165:10-3-10 REQUIRES:

1) PRIOR TO COMMENCEMENT OF HYDRAULIC FRACTURING OPERATIONS FOR HORIZONTAL WELLS, NOTICE GIVEN FIVE BUSINESS DAYS IN ADVANCE TO OFFSET OPERATORS WITH WELLS COMPLETED IN THE SAME COMMON SOURCE OF SUPPLY WITHIN 1/2 MILE;

2) WITH NOTICE ALSO GIVEN 48 HOURS IN ADVANCE OF HYDRAULIC FRACTURING ALL WELLS TO BOTH THE OCC CENTRAL OFFICE AND LOCAL DISTRICT OFFICES, USING THE "FRAC NOTICE FORM" FOUND AT THE FOLLOWING LINK: [OCCEWEB.COM/OG/OGFORMS.HTML](http://OCCEWEB.COM/OG/OGFORMS.HTML); AND,

3) THE CHEMICAL DISCLOSURE OF HYDRAULIC FRACTURING INGREDIENTS FOR ALL WELLS TO BE REPORTED TO FRACFOCUS WITHIN 60 DAYS AFTER THE CONCLUSION THE HYDRAULIC FRACTURING OPERATIONS, USING THE FOLLOWING LINK: [FRACFOCUS.ORG](http://FRACFOCUS.ORG)

INTERMEDIATE CASING

4/4/2018 - G71 - DUE TO THE KNOWN POTENTIAL RISK OF ENCOUNTERING AN OVER-PRESSURED ZONE IN THE MORROW SERIES IN THIS AREA, THE TECHNICAL MANAGER RECOMMENDS SETTING AN INTERMEDIATE STRING OF CASING IMMEDIATELY ABOVE THE MORROW SERIES

MEMO

4/4/2018 - G71 - PITS 1 & 2 - CLOSED SYSTEM=STEEL PITS PER OPERATOR REQUEST, PIT 2 - OBM RETURNED TO VENDOR, CUTTINGS PERMITTED PER DISTRICT

This permit does not address the right of entry or settlement of surface damages.

The duration of this permit is SIX MONTHS, except as otherwise provided by Rule 165: 10-3-1.

Rule 165: 10-3-4 (c) (7) (e) - The Operator shall give 24 Hours notice by telephone to the appropriate District Office of the Conservation Division as to when Surface Casing will be run.

011 23984 DOPPELGANGER 4\_9-15N-10W  
3HX

Category	Description
PENDING CD – 201801335	4/10/2018 - G58 - 4-15N-10W X658265 MSNLC, WDFD 10 WELLS NO OP. NAMED REC 4/3/2018 (MINMIER)
PENDING CD – 201801336	4/10/2018 - G58 - 9-15N-10W X658264 MSNLC, WDFD 10 WELLS NO OP. NAMED REC 4/3/2018 (MINMIER)
PENDING CD – 201801339	4/10/2018 - G58 - (I.O.) 4 & 9-15N-10W EST MULTIUNIT HORIZONTAL WELL X658265 MSNLC, WDFD (4-15N-10W) X658264 MSNLC, WDFD (9-15N-10W) 50% 4-15N-10W 50% 9-15N-10W NO OP. NAMED REC 4/3/2018 (MINMIER)
PENDING CD – 201801340	4/10/2018 - G58 - (I.O.) 4 & 9-15N-10W X658265 MSNLC, WDFD (4-15N-10W) X658264 MSNLC, WDFD (9-15N-10W) X165:10-3-28(C)(2)(B) MAY BE CLOSER THAN 600' TO PROPOSED WELL COMPL. INT (4-15N-10W) NCT 0' FNL, NCT 0' FSL, NCT 330' FWL COMPL. INT (9-15N-10W) NCT 0' FNL, NCT 165' FSL, NCT 330' FWL NO OP. NAMED REC 4/3/2018 (MINMIER)
SPACING – 658264	4/10/2018 - G58 - (640)(HOR) 9-15N-10W EST MSNLC EXT 643729 WDFD POE TO BHL (MSNLC) NCT 660' FB POE TO BHL (WDFD) NCT 165' FNL & FSL, NCT 330' FEL & FWL
SPACING – 658265	4/10/2018 - G58 - (640)(HOR) 4-15N-10W EXT 644506 MSNLC, WDFD POE TO BHL (MSNLC) NCT 660' FB POE TO BHL (WDFD) NCT 165' FNL & FSL, NCT 330' FEL & FWL


This permit does not address the right of entry or settlement of surface damages.

The duration of this permit is SIX MONTHS, except as otherwise provided by Rule 165: 10-3-1.

Rule 165: 10-3-4 (c) (7) (e) - The Operator shall give 24 Hours notice by telephone to the appropriate District Office of the Conservation Division as to when Surface Casing will be run.

011-23984

250'FNL-1320'FWL Section 4 Township 15N Range 10W I.M.



This information was gathered with a GPS receiver with  $\pm 1$  foot Horiz./vert. accuracy


DATUM: NAD-27  
LAT: 35°48'40.7"N  
LONG: 98°16'23.7"W  
LAT: 35.811310810°N  
LONG: 98.273252298°W  
STATE PLANE  
COORDINATES: (US Feet)  
ZONE: OK NORTH  
X: 1918978  
Y: 295438




BLAINE

County, Oklahoma

250'FNL-1320'FWL Section 4 Township 15N Range 10W I.M.



**NOTE:**  
The information shown herein is for construction purposes ONLY.



Operator: DEVON ENERGY PRODUCTION CO., LP  
Lease Name: DOPELGANGER 4\_9-15N-10W  
Topography & Vegetation: Loc. fell in sloping wheat field.  
Good Drill Site? Yes  
Reference Stakes or Alternate Location: Stakes Set None  
Best Accessibility to Location: From East off county road.  
Distance & Direction: From Kingfisher/Blaine County Line on St. Hwy. 33 go  $\pm 3$  miles West, then  $\pm 2$  miles South to the NE Cor. of Sec. 4-T15N-R10W.

**ELEVATION:**  
1316' Gr. at Stake NGVD29  
1317' Gr. at Stake NAVD88

FIRST PERF, LAST PERF, BOTTOM HOLE, AND DRILL PATH INFORMATION PROVIDED BY OPERATOR LISTED, NOT SURVEYED.

DATUM: NAD-27  
LAT: 35°48'40.7"N  
LONG: 98°16'23.7"W  
LAT: 35.811310810°N  
LONG: 98.273252298°W  
STATE PLANE  
COORDINATES: (US Feet)  
ZONE: OK NORTH  
X: 1918978  
Y: 295438

Date of Drawing: Mar. 1, 2018  
Invoice # 288616C Date Staked: Feb. 26, 2018 TR

**CERTIFICATE:**

I, Dan W. Rogers on Oklahoma Licensed Land Surveyor and an authorized agent of Topographic Land Surveyors of Oklahoma, do hereby certify to the information shown herein

Oklahoma Lic. No. 1200






# TOPOGRAPHIC LAND SURVEYORS OF OKLAHOMA

Surveying and Mapping for the Energy Industry  
13800 Wireless Way, Oklahoma City, OK 73134 [www.topographic.com](http://www.topographic.com)  
Telephone Numbers: Local (405) 843-4847 Toll Free (800) 654-3219

## LOCATION & ELEVATION VERIFICATION MAP



Sec. 4 Twp. 15N Rng. 10W IM

County BLAINE State OK

Operator DEVON ENERGY PRODUCTION CO., LP

Description 250'FNL-1320'FWL

Lease DOPPELGANGER 4\_9-15N-10W 3HX

Elevation 1316' Gr. at Stake NGVD29  
1317' Gr. at Stake NAVD88

Above Background Data from  
U.S.G.S. Topographic Map

Scale: 1"=2000'

Contour Interval 10'

When elevation is shown hereon it is the ground  
elevation of the location stake.  
Review this plat and inform us immediately of  
any possible discrepancy.



LAND SURVEYORS OF OKLAHOMA


Feb. 26, 2018



# TOPOGRAPHIC LAND SURVEYORS OF OKLAHOMA

Surveying and Mapping for the Energy Industry  
13800 Wireless Way, Oklahoma City, OK 73134 [www.topographic.com](http://www.topographic.com)  
Telephone Numbers: Local (405) 843-4847 Toll Free (800) 654-3219

## VICINITY MAP



Scale: 1" = 3 Miles

Sec. 4 Twp. 15N Rng. 10W IM

County BLAINE State OK

Operator DEVON ENERGY PRODUCTION CO., LP



LAND SURVEYORS OF OKLAHOMA

13800 WIRELESS WAY, OKLA. CITY, OKLA. 73134 \* LOCAL (405) 843-4847 \* OUT OF STATE (800) 654-3219  
Certificate of Authorization No. 1293 LS

County, Oklahoma


**NOTE:**  
The information shown herein is for construction purposes ONLY.



T 15 N - R 10 W  
(INDIAN MERIDIAN)

PLAT SHOWING

PROPOSED PAD AREA IN THE  
NW/4 OF SECTION 4, T15N - R10W &  
SW/4 OF SECTION 33, T16N - R10W  
BLAINE COUNTY, OKLAHOMA



(A) DEVON ENERGY  
PRODUCTION CO., LP  
KRAKEN 33\_28-16N-10W 2HX  
250'FNL-1200'FWL  
Elev. 1318' Gr.


(B) DEVON ENERGY  
PRODUCTION CO., LP  
KRAKEN 33\_28-16N-10W 3HX  
250'FNL-1230'FWL  
Elev. 1318' Gr.

(C) DEVON ENERGY  
PRODUCTION CO., LP  
DOPPELGANGER 4\_9-15N-10W 2HX  
250'FNL-1290'FWL  
Elev. 1316' Gr.

(D) DEVON ENERGY  
PRODUCTION CO., LP  
DOPPELGANGER 4\_9-15N-10W 3HX  
250'FNL-1320'FWL  
Elev. 1316' Gr.

(E) DEVON ENERGY  
PRODUCTION CO., LP  
DOPPELGANGER 4\_9-15N-10W 4HX  
250'FNL-1350'FWL  
Elev. 1316' Gr.

SECTION 33  
SW/4



NOTE:

The information shown herein is  
for construction purposes ONLY.

				This plat was prepared exclusively for		SCALE: 1"=100'	
				<b>DEVON ENERGY PRODUCTION CO., LP</b>		DATE: 2/28/18	
NO.	REVISION	DATE	BY	and may not be relied upon by any other entity without the written consent of Topographic Land Surveyors of Oklahoma		INVOICE NO.: 288616	
SUR. BY: JW 2/26/18				SURVEYING AND MAPPING BY		FILE NAME: L2674B.DWG	
DRAWN BY: TR				<b>TOPOGRAPHIC LAND SURVEYORS OF OKLAHOMA</b>		DWG NO.:104059-L2-674-B	
APPROVED BY: DR				13800 Wireless Way, Okla. City, OK. 73134 (405) 843-4847		SHEET 1 OF 1	
				Certificate of Authorization No. 1293 LS			